

Governance House · building program

SH-SITE-0001-B01 | same footprint, cores and access strategy across floors

MODELLED NOT AS BUILT

SH-SITE-0001-B01-L02 · Enterprise collaboration

1,152 m² gross · 20 planned peak · MODELLED FITOUT NOT EXISTING

SH-SITE-0001-B01-L01 · Arrival and institutional work

1,152 m² gross · 35 planned peak · MODELLED FITOUT NOT EXISTING

STRUCTURE

6 m planning grid; slab/column sizes not engineered

VERTICAL SERVICES

6 m end service bays; 3 m central corridor; protected stairs and lift stack unchanged

PROGRAM

2 levels; 2,304 m² gross. Vertical access follows the floor/core plan. Mechanical loads and structure are design dependencies.

CONSTRUCTION STATE

September 2026: modelled concept only. Acquisition, permits, shell, fit-out and commissioning dates are null until supported. 2031 and 2036 are capacity horizons, not completion promises.