

INTERMEDIATE UPGRADING AND BLENDING / BUILDING PROGRAM

CONCEPT REVIEW / R02

Coordinated floor stack • Same footprint and fixed service cores

L01 / BOUNDED DEVELOPMENT AND MIXED-PRODUCT UPGRADING

9,300 gross sq ft / 2 workplaces / 6 planned peak

Controlled intermediate preparation · Blending and upgrading work envelope · Batch verification and product sampling · Operating records and local supervision

PROGRAM

1 floors / 9,300 gross sq ft. Staff workplaces, training, meeting, dining and residence remain separate capacities.

STRUCTURE / SERVICES

Concept steel frame on 6 m bay grid; industrial roof spans, lifting capacity, slab loading and foundations require engineering. No installed lifting plant asserted.

CORE COORDINATION

Two independent end exit/service bays; 3 m central circulation separates personnel from process rooms. Wet, ventilation and utility zones remain outside material handling. No classified process or hazardous inventory assumed.

SEPTEMBER 2026

Concept design only. Parcel, tenure, permit, construction and occupancy evidence remain separate. No completed facility is asserted.

01 ONE BUILDING

Floorplates and service shafts align vertically. Detailed engineering and fire strategy remain coordinated design dependencies.

SH-SITE-0005-B03 / LOCAL CONCEPT STACK / NOT TO SCALE