

# THE BIG SHED / BUILDING PROGRAM

Coordinated floor stack • Same footprint and fixed service cores

CONCEPT REVIEW / R02

## L01 / RESEARCH, INTEGRATION AND PROTOTYPE WORK

19,375 gross sq ft / 12 workplaces / 20 planned peak

Prototype fabrication and integration · Instrumented test hall · Controls and measurement benches · Instrumentation clean benches · RF and communications bench work · Research write-up and data review · Experiment readiness and debrief

### PROGRAM

1 floors / 19,375 gross sq ft. Staff workplaces, training, meeting, dining and residence remain separate capacities.

### STRUCTURE / SERVICES

Concept steel frame on 6 m bay grid; industrial roof spans, lifting capacity, slab loading and foundations require engineering. No installed lifting plant asserted.

### CORE COORDINATION

Two independent end exit/service bays; 3 m central circulation separates personnel from process rooms. Wet, ventilation and utility zones remain outside material handling. No classified process or hazardous inventory assumed.

### SEPTEMBER 2026

Concept design only. Parcel, tenure, permit, construction and occupancy evidence remain separate. No completed facility is asserted.

### 01 ONE BUILDING

Floorplates and service shafts align vertically. Detailed engineering and fire strategy remain coordinated design dependencies.

SH-FAC-FORT-BIG / LOCAL CONCEPT STACK / NOT TO SCALE